

BECKER COUNTY MATERIAL RECOVERY FACILITY
24413 CO RD 144
DETROIT LAKES, MN



MBA PROJECT NO. 17002

ADDENDUM NO. 2

Bid Packages Covered by This Addendum:
SINGLE PRIME CONTRACTOR

July 13, 2017

Acknowledge receipt of this Addendum by inserting its number in space provided on Bid Form. Failure to do so may subject Bidder to disqualification. This Addendum forms part of Bidding Documents and modifies them as follows.

The following additions, deletions and / or changes shall be made to the SPECIFICATIONS:

SPECIFICATIONS

Section 13 3419 – Metal Building Systems

1. 2.10 Roof and Wall Insulation: Omit and replace Paragraph B with:
 - A. Wall insulation to be R-13 continuous insulation over the exterior of the girt. Cavity fill the remainder of wall girt with batt insulation. Provide white vinyl support system with straps.

The following additions, deletions and / or changes shall be made to the DRAWINGS:

SHEET S4.1

1. Detail 17: Slab to be 6" concrete in lieu of 8". Reinforcing to remain the same.

END OF ADDENDUM NO. 2